




Mechanical Loc Installation



Mechanical Loc is a commercial grade panel that is mechanically seamed and installed with a concealed clip system. This panel is ideal for shallow sloped roofs. Available in 2", 1.5" and 1" seam heights, the Mechanical Loc panel system creates long clean lines with wide spans, provides superior weather-tight protection, and allows for thermal expansion and contraction with a floating clip system. Mechanical Loc is available with minor ribs and comes in variable widths. Mechanical Loc requires on-site seaming.

Mechanical Loc Trims: Refer to our 2", 1.5" & 1" Trim Collections for all trim profiles associated with Mechanical Loc Panels

Installation Drawings: Basic installation drawings are attached to this document. Specific details and further information may be required as per site requirements.

FORMA STEEL

Mechanical Loc Panel Installation

Obstacle Removal

Remove downspouts to create a clear workspace for installing the siding. Trees, shrubs and any other objects that could get in the way should also be safely removed. Remove windowsill extensions where necessary.

Roof Preparation

Ensure that the surface is even. The working surface should be secured with fasteners, and clear of debris such as old paint, putty or caulking buildup. Make sure the house wrap or water barrier is installed according to building codes before installing the panels over top.

Product Preparation:

Remove the protective film prior to installation. Review panel lengths in reference to the cut sheet.

Cutting:

Because the underside is flatter, it is recommended that roofing and siding be cut from this side. A power saw, nibbler, snips or profile shear may be used. Be sure to clean metal filings from off the panels to prevent unsightly stains.

Storage Instructions:

If the panels are not going to be used immediately, they should be stored in a dry well ventilated area. If it is not possible to store the material inside, block up the panels to allow air movement around the packages. Also raise one side of the bundles to ensure positive draining, and use a good quality cover (other than plastic) anchored loosely to protect the material and still allow ventilation. Store away from aggressive substances and any other materials that could contaminate the surface of the panels.

Application Precautions:

Metal installed with screw fasteners should be fastened onto a solid backing. Avoid installing directly over green, damp or ACQ lumber, porous insulation or other damaging materials. The use of a moisture barrier (such as Ice & Water Shield) is recommended in such situations. Strong chemicals, fertilizers, manure, some soils, and lime may cause premature deterioration. Installation near such materials is not recommended.

Warning:

Material is slippery and has sharp edges, use extreme caution when handling or installing. Avoid working with sheet metal products on windy days.

Mechanical Loc Installation Tools Available:

Forma Steel has many tools available for rent to make sure every installation goes as easy as possible. Below are our available tools for installing standing seam panels. Contact our Forma Steel Order Desk to reserve a trailer or tools for your next panel installation.


SWENSON SHEAR

SNAPTABLE PRO

The SnapTable is an all-in-one panel preparation system for preparing to install standing seam metal roofing. This tool is designed to perfect and speed-up your panel preparation process while producing factory like cuts.

This complete system is made up of 3 key components: the standing seam notcher, the panel cutter, and the eave and valley hemmer.

The Towable SnapTable Pro provides the highest quality notching, cutting and hemming for any commercial, industrial or residential job. It is equipped to notch, cut & hem your snap lock and standing seam profiles at your eaves, hips and valleys.









BIEGETEC DOUBLE SEAM CLOSER





The **Double Seam Closer PVC** tool is for closing both Stages by Double Standing Seam profiles with no surface damage.

BIEGETEC ACCUSEAMER






The Accuseamer is the perfect hand held tool for effortless seaming of single and double lock standing seam and works with a conventional cordless power drill. Seams up to 180ft / minute versus a typical seamer at 35 ft / minute.




THERMAL GAP INSTALLATION CHART



THERMAL "GAP" INSTALLATION CHART (In inches) - ALUMINUM								
For determining proper expansion/contraction gap at panel ends during installation								
Distance Material Temperature (Surface Temperature) During Installation								
from fixed	Но	ot	W	arm	Cold			
point in feet	>100)° F	100° t	o 50° F	<50° F			
10	0.279	1/4	0.139	1/8	0.000	0		
20	0.557	9/16	0.279	1/4	0.000	0		
30	0.836	13/16	0.418	7/16	0.125	1/8		
40	1.115	1 1/8	0.557	9/16	0.125	1/8		
50	1.393	1 3/8	0.697	11/16	0.188	3/16		
60	1.672	1 11/16	0.836	13/16	0.188	3/16		
70	1.950	1 15/16	0.975	1	0.250	1/4		
80	2.229	2 1/4	1.115	1 1/8	0.250	1/4		
90	2.508	2 1/2	1.254	1 1/4	0.375	3/8		
100	2.786	2 13/16	1.393	1 3/8	0.375	3/8		
* Chart based on temperature differential of: 180 degrees F								
* Coefficient of thermal expansion for alum.: 0.0000129								





CHK DRW DRAWING STATUS DATE #

NOTES

This is a copyright drawing and shall not be reproduced in any form without written permission from Forma Steel

Contractor to check and verify all the dimensions before construction, any errors and omissions shall be reported immediately

Do not scale drawing

All construction shall be in accordance with latest codes.

SIGNATURE DATE NAME OWNER APPROVAL CONTRACTOR APPROVAL: **MECHANICAL PANEL DRAWING** LOC

SD1 11-14-2019


NOTES: LIGHT GAUGE STEEL CLADDING WITH WIDE FLAT PANS MAY EXHIBIT OIL CANNING WHICH CAN AFFECT THE AFFECT THE AESTHETICS OF THE BUILDING DESIGN

OIL CANNING WILL VARY DEPENDING ON THE TIME OF DAY AND ANGLE OF VIEWING AND IS USUALLY MORE NOTICEABLE IN DARKER COLOURS

OIL CANNING WILL ALSO BE MORE PREVALENT IN WIDER PANS AND LONGER SHEET RUNS, BUILDING DESIGNERS AND HOMEOWNERS SHOULD BE AWARE OF THIS AND TAKE INTO CONSIDERATION

OIL CANNING IS NOT A REASON FOR MATERIAL REJECTION





						APP	
						CHK	
						DRW	
						NSO	
						DATE DRAWING STATUS DSN DRW CHK APP	
						#	
NOTES							

This is a copyright drawing and shall not be reproduced in any form without written permission from Forma Steel

Contractor to check and verify all the dimensions before construction, any errors and omissions shall be reported immediately

Do not scale the drawing

All construction shall be in accordance with latest codes.

	NAME		SIGNATURE	DATE
OWNER APPROVAL:				
CONTRACTOR APPROVAL:				
CONSULTANT APPROVAL:				
MECHAN	ICAL	DRAWING	PANEL	

OIL CANNING IS NOT A REASON FOR MATERIAL REJECTION

NOTES: LIGHT GAUGE STEEL CLADDING WITH WIDE FLAT PANS MAY EXHIBIT OIL CANNING WHICH CAN AFFECT THE AFFECT THE AESTHETICS OF THE BUILDING DESIGN


OIL CANNING WILL VARY DEPENDING ON THE TIME OF DAY AND ANGLE OF VIEWING AND IS USUALLY MORE NOTICEABLE IN DARKER COLOURS

OIL CANNING WILL ALSO BE MORE PREVALENT IN WIDER PANS AND LONGER SHEET RUNS, BUILDING DESIGNERS AND HOMEOWNERS SHOULD BE AWARE OF THIS AND TAKE INTO CONSIDERATION

11-14-2019

SD2





					APP		
					CHK		
					DRW		
					NSO		
					DATE DRAWING STATUS DSN DRW CHK APP		
					DATE		
					#		
NOTES							

This is a copyright drawing and shall not be reproduced in any form without written permission from Forma Steel

Contractor to check and verify all the dimensions before construction, any errors and omissions shall be reported immediately

Do not scale the drawing


All construction shall be in accordance with latest codes.

SIGNATURE NAME DATE OWNER APPROVAL CONTRACTOR APPROVAL: **MECHANICAL GABLE** LOC **STARTER**


SD3 01-06-20


























						APP
						CHK
						DRW
						NSO
						DATE DRAWING STATUS DSN DRW CHK APP
						٠
						#
NOTES						

NOTES

This is a copyright drawing and shall not be reproduced in any form without written permission from Forma Steel

Contractor to check and verify all the dimensions before construction, any errors and omissions shall be reported immediately

Do not scale the drawing

All construction shall be in accordance with latest codes.

	NAME		SIGNATURE	DATE
OWNER APPROVAL:				
CONTRACTOR APPROVAL:				
CONSULTANT APPROVAL:				
MECHAN	IICAL	DRAWING	VENTED HIG	Н
1.00	· •		FAVF	

SD8 01-06-20



